No.	Particulars	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		Rs. a. p.
24	Providing and fixing iron ladder to the top terrace as per design	L. S.	..	..	
25	Providing and fixing B.S. slabs 4" thick 2 line dressed at top 1½' square set diagonally over a layer of 3" of 1:2 lime concrete in portico (flooring)	Sqr.	50 0 0	1.80	

B. R. GARUDACHAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 12th April 1939.

The attention of the public is drawn to the Notification calling for tenders for Restoring Kyadigunte Major Tank, Register No. 139, Pavagada Taluk, published in pages 739 and 740, Part VI of the *Mysore Gazette*, dated 20th April 1939.

The tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 29th April 1939.

The earnest money required for the work is Rs. 270 which should be credited to the treasury to the head "17 (*a*) Public Works Deposits" and the challan enclosed with the tender.

P. RAJAGOPALAN,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 21st April 1939.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 10th May 1939, for constructing a mortuary behind the dissection Theatre in the Medical College, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing a mortuary behind the dissection Theatre in the Medical College, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 250 only in cash or Government Security, Municipal Debentures, Post Office Cash Certificates (at cash payment value at the time of deposits and not face value), as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form. The amount of earnest money should be paid direct to treasury and the duplicate treasury challan submitted separately along with the tender.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 10th May 1939 at 4 P.M. The final acceptance of the tender will rest with the Government who do not bind themselves to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of June 1939, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 10 per day of delay which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the Assistant Engineer in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs, or measures, shoring and other requisite protection during the progress of the work.
(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with their own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.
(10) Afford facilities to any other parties employed upon the work so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

Note.—(*b*) It is the business of the contractors to make their own arrangements for quarries and supplies of materials.

23. The rates for wood-work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 3,000 will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore teak is as follows :—

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″	3	4	0	„
(2*a*) Do 3″×5″ to 4″×7″	3	12	0	„
(3) Planks 1″ to 1¾″ to required sizes	4	8	0	„

25. Only Chamundi Brand cement should be used for all works requiring this nature.

26. Such of the tenders which do not clearly quote with detailed specifications for all the items without exception will not be considered.

Approximate quantities of estimate for constructing a mortuary behind the Dissection Theatre in the Medical College, Mysore.

Sl. No.	Items of work	Unit	Quantity	Rate
				Rs. a. p.
1	Earthwork excavation for foundation in ordinary soil and filling in basement with watering and consolidating, etc. ..	C.yd.	110	
2	Laying in granite jelly lime mortar concrete 1 : 2½ in layers of not more than 6″ and tamping, etc., complete ..	C.ft.	895	
3	Size stone in lime mortar for foundation	,,	1,371	
4	Size stone in lime mortar for basement	,,	628	
5	Two lines dressing to basement exposed faces alround ..	S.ft.	217	
6	Cement pointing to basement after raking joints 1½″ deep and cut to neat lines	Sqr.	2·17	
7	Providing and fixing, burnt stone slabs 6″ thick all sides, one line dressed inside faces 2 lines dressed on exposed faces, etc., complete	S.ft.	265	
8	Burnt brick in lime mortar for superstructure	C.ft.	2,251	
9	R. C. C. works with 1 per cent reinforcement 1 : 2 : 4 jelly to be of broken granite metal, etc., complete	,,	68	
10	Cement concrete slabs 1 : 2 : 4 jelly to be of granite metal ..	,,	159	
11	Providing and fixing teakwood doors with 3″×5″ frames with panelled shutters 1½″ thick, including, iron bolts parliamentary hinges, etc., complete	S.ft.	300	
12	Providing and fixing, teakwood windows with 3″×5″ frames with double shutters glazed inside and panelled 1½″ thick shutters outside with brass parliamentary hinges, bolts, hooks, etc., complete	,,	279	
13	Providing and fixing teakwood semi-circular galzed perforated ventilators	,,	42	
14	Providing, hoisting and fixing, R. S. girders of B. S. S. tested, with one coat of anti-corrosive paint and boxing with terrace bricks in cement mortar plastering, coning, etc., complete..	Cwt.	23·36	
15	Wire cut bricks in cement mortar arch work	C.ft.	50	
16	Roofing with R. B. C. terrace with ½″ iron bars at 4½″ centre to centre with 2″ of cement concrete 3″ to 4″ of kappi laid to required slope on top 2 courses of flat tiles, plastering, etc., complete	Sqr.	11·67	
17	Flooring with 1½″ cement concrete 1 : : 4 tiles to be granite over 4″ lime concrete with tapping of red cement ¼″ finished smooth	Sqr.	9·43	
18	Plastering with chunam mortar smooth including rounding of corners if necessary, plaster on outer faces being ground with yellow ochre to a cream tint etc., complete	,,	53·81	
19	White and colour washing	,,	53·81	
20	Providing and fixing R. C. C. fret work ventilators	S.ft.	19	
21	Painting with 2 coats of superior Delux paint	Sqr.	15·12	
22	Providing plain parapet wall 4½″ to 9″ thick and 1½′ high including plastering, white and colour washing, etc., complete ..	R.ft.	133	
23	Providing R. C. C. chajja projection 3′ beyond the wall 4″ to 5″ thick, anchoring in to walls with necessary reinforcements and counter weight, including plastering and edge cornice etc., complete (measurements for exposed faces only)	S.ft.	48	
24	Providing and fixing cement asbestos rain water down pipes, including heads, bends, etc., complete	R.ft.	109	

M. A. RAMANUJAM,
Assistant Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 13—14*th April* 1939.

The attention of the public is invited to the Notification published in page 741 of Part VI of the *Mysore Gazette*, dated 20th April 1939, calling for tenders for the collection of materials on Salem-Bellary and Bangalore-Dharwar Roads.

The last date is 29th April 1939.

S. RAMASWAMY,
Executive Engineer.